KADUR FOREST DIVISION.

Abstract Notification dated 3rd February 1938.

The attention of the public is invited to the detailed notification dated 3rd February 1938 regarding the sale of timber in Kadur Depot on 8th March 1938 published on pages 184-185, Part VI of the *Mysore Gazette* dated 10th February 1938.

M. A. MUTHANNA,
District Forest Officer.

ENGINEERING DEPARTMENT

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notice dated 29th January/2nd February 1938.

The attention of the public is invited to the notification calling for tenders for the labour portion of the work for "laying pipe lines for giving water supply to Shikarpur Town, Shimoga District" published in Part VI, pages 218-219 of *Mysore Gazette* dated 10th February 1938.

The last date of receiving tenders is fixed on the 22nd February 1938.

Notification dated 9th February 1938.

Notice is hereby given that sealed tenders will be received at the office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 25th February 1938, for constructing 1st stage drains in Kolar Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1938.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for constructing 1st stage drains in Kolar Town," in default of which; the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Director of Public Health will be final and legally binding.

Estimate of the approximate quantities for constructing 1st stage Drains in Kolar Town.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Constructing silk pattern drains with 3″ thick burnt stone slab checks at sides and forming U shaped drain at the centre with $1\frac{1}{2}$″ thick cement concrete in the proportion of 1 : 2 : 4 on 3″ thick surki concrete bed and the surface plastered over by $\frac{1}{2}$″ thick cement mortar in the proportion of 1 : 3 including earthwork, etc. complete as per design—				
	4″(1) section design	R.ft.	..	1,330	
	5″(2) do	R.ft.	..	180	
2	3″ Section design with old slabs of the existing drains inclusive of removing, spilitting to required width and using the same, etc., complete	R.ft.	..	2,930	
3	Constructing 3″ section semi-peg top drain with cement concrete in the proportion of 1 : 2 : 4 at bed and sides and cement plastering the exposed surface including earthwork, etc., complete as per design	R.ft.	..	670	
	Repairing the existing box drain 2′ wide by forming U shaped drain as per design with $4\frac{1}{2}$″ thick cement concrete in the proportion of 1 : 2 : 4 and the surface plastered over by $\frac{1}{2}$″ thick cement mortar in the proportion of 1 : 3 and pointing side size stone walls with cement mortar	R.ft.	..	550	

Notification dated 9th February 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 25th February 1938, for constructing drains in Chamarajnagar. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1938.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 225 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for constructing drains in Chamarajnagar," in default of which, the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Director of Public Health will be final and legally binding.

Estimate of the approximate quantities for constructing Drains at Chamarajnagar Town.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Constructing 3″ section semi-peg top drain with cement concrete in the proportion of 1 : 2 : 4 at bed and sides and cement plastering the exposed surface including earth work, etc. complete as per design	R.ft.	..	6,590	
2	Repairing the existing slab drain by removing and resetting 30 per cent of slabs and providing cement concrete $1\frac{1}{2}' \times \frac{3}{4}' \times \frac{1}{4}'$ at joints including excavation and providing baby jelly cement concrete for bottom portion $\frac{1}{4}' \times \frac{1}{8}'$ and cement pointing joints, etc. complete ..	R.ft.	..	500	
3	Repairing the existing box drain by forming U shaped drain at the centre with about 3″ thick cement concrete in the proportion of 1 : 2 : 4 over 3″ thick lime concrete bed and the surface plastered over by $\frac{1}{2}$″ cement plastering in the proportion of 1 : 3	R.ft.	..	350	

N. KRISHNIENGAR,
Sanitary Engineer.

WATER SUPPLY DIVISION.

Notification dated 9th February 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water Supply Division, up to 26th February 1938, for excavating, removing, cleaning, carting and stacking 15″ steel pipes from the "Y" Tank main to Combined Jewell Filters. An approximate estimate of quantities for each building is given below. These quantities are not guaranteed. The work should be completed by the end of April 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office Water Supply Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 275, in cash or Government, Promissory Notes, as earnest money, and be superscribed "Tender for excavating, removing, carting and stacking 15″ steel pipes from the "Y" Tank to Combined Jewell Filters" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than the estimated rate will not be accepted.